Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
134	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 7.7 / 7.12 Third Floor	Sqm	22.10	5025.00	Rupees Five Thousand Twenty Five Only
135	Providing and fixing in position collapsible steel shutters with single or double leaf with vertical channel 20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6 mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stoppers, handles on both sides with 7.5cms openings at 10 cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications. - Terrece Floor	Sqm	11.10	5032.00	Rupees Five Thousand Thirty Two Only
136	Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 m - Ground Floor	Sqm	262.20	3553.00	Rupees Three Thousand Five Hundred Fifty Three Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
137	Providing and fixing pull and push type rolling shutters of approved make out of 18 guage, 75mm wide cold rolled steel laths of convex corrugation, with side guides and bottom rail, with interlocking arrangements for steel laths by means of alternate clips, suspension shaft with High tension coil type springs two numbers, mounted on specially designed pipe shaft, with bracket plates, guide channels, ball bearing arrangements, for inside & outside locking with push & pull operations complete including pulling hooks, 4Nos. handles with all fittings and accessories, painted with a coat of red lead paint (without top cover) cost of materials, labour, HOM of machinery complete as per specifications. Shutter size 3mx2.8 m Specification No. KBS 7.10 / 7.12 First Floor	Sqm	465.60	3559.00	Rupees Three Thousand Five Hundred Fifty Nine Only
138	Providing and fixing Stainless steel 304 Grade for staircase railing, Balconys Ramps with hand rails 50mm dia 16 guage hollow pipe welded to vertical hollow 50mm dia pipe of 16 guage, stainless steel vertical pipe spaced at 1.20m regular intervals, and 5 Nos of 25mm dia. Stainless steel hollow horizontal pipe are welded to vertical 50mm dia hollow pipe. The entire assembly is fixed to staircase concrete by using expansion bolts by drilling concrete etc., complete including cost of materials, labour, HOM of machineries and electrical charges etc., complete as per specification All Floors	Sqm	36.00	7637.00	Rupees Seven Thousand Six Hundred Thirty Seven Only
139	Fixing of door frame in an existing opening including embeeding frame in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications.Second Floor	Sqm	6.00	1312.00	Rupees One Thousand Three Hundred Twelve Only
140	Fixing of door frame in an existing opening including embeeding fraine in floor and walls after cutting masonry for holdfasts for embedding holdfast in cement concrete 1:3:6 of 20mm and down size granite metal painting two coats of coal tar to sides of frame, making good the damages to walls and floor as required and disposal of the debries with lead upto 50 m. including cost of materials, labour charges, complete as per specifications.Third Floor	Sqm	6.00	1314.00	Rupees One Thousand Three Hundred Fourteen Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Wo
1	2	3	4	5	
141	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet.Point wirig using class A Materials a) Short point upto 3.0M from tapping point to outlet via switch box	Each	85.00	166.00	Rupe Hundred On
142	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet.Point wirig using class A Materials b) Medium point above 3.0M upto 6.0M from tapping point to outlet via switch box	Each	120.00	247.00	Rupees Hundred Fort Only
143	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet.Point wirig using class A Materials c) Long point above 6.0M upto 10.0M from tapping point to outlet via switch box	Each	60.00	384.00	Rupees Thre Hundred Eigh Four Only
144	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet.Point wirig using class A Materials d) Two outlet in a row, above 3.0M upto 6.0M from tapping point to outlet via switch box	Each	20.00	486.00	Rupees Four Hundred Eighty Si Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
145	Supplying and wiring adopting loop system in existing PVC Conduit / casing caping using 1100V grade, copper conductor flecxible multistrand FRLS PVC insulated, 2x.1.5Sqmm cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/ PVC round block.complete for each outlet.Point wirig using class A Materials e) Three outlet in a row, above 6.0M upto 10.0M from tapping point to outlet via switch box	Each	15.00	682.00	Rupees Six Hundred Eighty Two Only
146	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.Cwall a)1-3Way	Each	10.00	105.00	Rupees One Hundred Five Only
147	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/Cb)6 Way	Each	20.00	139.00	Rupees One Hundred Thirty Nine Only
148	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/Cc) 8Way	Each	50.00	161.00	Rupees One Hundred Sixty One Only
149	Supplying and flush mounting powder coated / galvanized metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/Cd) 10-12Way	Each	30.00	183.00	Rupees One Hundred Eighty Three Only
150	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. a)1-3Module	Each	10.00	125.00	Rupees One Hundred Twenty Five Only
151	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.b)6 Module	Each	20.00	199.00	Rupees One Hundred Ninety Nine Only
152	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.c)8 Module	Each	50.00	230.00	Rupees Two Hundred Thirty Only
153	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.d) 10Module	Each	20.00	261.00	Rupees Two Hundred Sixty One Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
154	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box.e) 12Module	Each	10.00	307.00	Rupees Three Hundred Seven Only
155	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material a) 6Amps one Way	Each	200.00	72.00	Rupees Seventy Two Only
156	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material b) 6Amps Two way	Each	6.00	100.00	Rupees One Hundred Only
157	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material c) 6Amps 3way socket	Each	100.00	109.00	Rupees One Hundred Nine Only
158	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material d) Steeped fan Regulator	Each	110.00	329.00	Rupees Three Hundred Twenty Nine Only
159	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material e) 16Amps one way switch	Each	70.00	131.00	Rupees One Hundred Thirty One Only
160	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material f) 6Amps Bell push	Each	2.00	100.00	Rupees One Hundred Only
161	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material g) 6/16Amps universal socket	Each	30.00	169.00	Rupees One Hundred Sixty Nine Only
162	Supplying and fixing of modular switch/socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 Group 'A' Material h) TV/Telephone socket	Each	6.00	94.00	Rupees Ninety Four Only
163	Supply and fixing of 6Amps bell buzzer on existing switch board.	Each	4.00	134.00	Rupees One Hundred Thirty Four Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
164	Supplying following size heavy guage PVC conduit pipe and following thick confirming to IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessary a) 19mm dia 2mm thick	Each	2000.00	49.00	Rupees Forty Nine Only
165	Supplying following size heavy guage PVC conduit pipe and following thick confirming to IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessaryb) 25mm dia 2mm thick	Each	1000.00	66.00	Rupees Sixty Six Only
166	Supplying following size heavy guage PVC conduit pipe and following thick confirming to IS 2509 with suitable size bends, Metal/PVCjunction boxes, adhesive paste etc, and running before concreting the slab. The conduit should be tied to the reinforcement rods by using binding wires and unused ways of junction boxes and pipe ends should be covered using PVC end enclosures run with 18SWG GI fish wire where ever necessaryc) 32mm dia 2.5mm thick	Each	65.00	103.00	Rupees One Hundred Three Only
167	Supplying heavy gauge pvc conduit pipe ...dia...mm thick with suitable size bends, metal Junction boxes adhesive paste etc..,by groove cutting in the wall and fixing by bracing U & J hooks and Cement plastering upto the wall surface and run wirh 18 SWG GI fish wire run throughout the conduit where ever necessary. 19/ 20 mm dia 2mm thick	Rmtr	2000.00	64.00	Rupees Sixty Four Only
168	Supplying heavy gauge pvc conduit pipe ...dia...mm thick with suitable size bends, metal Junction boxes adhesive paste etc..,by groove cutting in the wall and fixing by bracing U & J hooks and Cement plastering upto the wall surface and run wirh 18 SWG GI fish wire run throughout the conduit where ever necessary.25 mm dia 2mm thick	Rmtr	500.00	67.00	Rupees Sixty Seven Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
169	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-A. a) 1.5sqmm	Rmtr	2000.00	21.00	Rupees Twenty One Only
170	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-Ab) 2.5sqmm	Rmtr	3000.00	34.00	Rupees Thirty Four Only
171	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multisand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of Group-Ac) 4sqmm	Rmtr	1500.00	48.00	Rupees Forty Eight Only
172	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.I - Single Door 8Way SP &N -	Rmtr	60.00	995.00	Rupees Nine Hundred Ninety Five Only
173	Supplying and fixing regular MCB distribution boards on wall / wood board / flush mounting using required clamps, bolts, nuts etc., with provision for fixing suitable type capacity MCB's single phase / 3 phase / single door with powder coated painting. Made out of 14 SWG MS enclosure.II - Double Door 6Way TP & N	Rmtr	2.00	3296.00	Rupees Three Thousand Two Hundred Ninety Six Only
174	Supplying, fixing and wiring Earth Leakage Miniature Circuit Breaker (ELMCB) 240/450V uoto 300mA sensitivity on exisiting wood/panel board. 32- 40 Amps 4 pole	Rmtr	1.00	3375.00	Rupees Three Thousand Three Hundred Seventy Five Only
175	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. confirming to IEC 60898 - 5-32A SP MCB	Rmtr	60.00	480.00	Rupees Four Hundred Eighty Only
176	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. confirming to IEC 60898 5-32AMPS DB MCB	Rmtr	2.00	976.00	Rupees Nine Hundred Seventy Six Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
177	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. confirming to IEC 60898 5-32AMPS TPN MCB	Rmtr	1.00	1778.00	Rupees One Thousand Seven Hundred Seventy Eight Only
178	Supplying Patti type fluorescent tube light fitting of 4' - suitable for 28 W fluorescent tube fitting made out of MS sheet and stove enamelled withHF Electronic Ballast locking type brass contact holder mounted on double fold typebase fully y wired for use on 230V AC supply including T5 fluorescent tube	Nos	100.00	769.00	Rupees Seven Hundred Sixty Nine Only
179	Supplying and fixing PBBC bakelite straight or slant batten holder and wiring with 60W/230 VOLTS/18W CFL lamp	Each	25.00	101.00	Rupees One Hundred One Only
180	Supplying and. fixing cast Aluminium round or oblong type bulk head fitting with GI wire guard, glass cover with 15Watts 230V CFL lamp as required	Each	10.00	1094.00	Rupees One Thousand Ninety Four Only
181	Supply of 2'x2' LED recessed luminaire with ...Watts system wattage. Housing shall be with pressure die cast aluminum alloy with corrosion proof resistant polyester power coated. Driver operates with voltage range from 100V to 270V 50/60 Hz with short circuit, overload & mis-wiring protection. Lumen Maintenance of 70% at 50000 Hrs. Injection moulded poly carbonate diffuser for better mechanical stability, light transmission & avoid pot hole effect. Junction temperature shall be < 70 degree Celsius. Driver is on constant current driver @ 0.06A with PF > 0.92 with line voltage @ 220-240V @ 50/60Hz, driver efficiency > 85% & THD<15%. LED Efficiency > 130 lm/W at 1W & Fixture Efficiency >75lm/w with CRI > 75 with injection moulded Polycarbonate lens with < 80mm depth. 5 years Warranty against any manufacturing defect working under standard electrical condition LED modular down light 2'x2'-36 watts	Each	6.00	9474.00	Rupees Nine Thousand Four Hundred Seventy Four Only
182	Supplying CFL Mirror light fitting with 1x11W CFL lamp, choke, perspex cover and completely wired for use on 230V 50Hz AC Supply.	Each	4.00	745.00	Rupees Seven Hundred Forty Five Only
183	Supplying of 1440rpm heavy duty eahust fan with bracket blades suitable for operate on 230V 50Hz, AC Supply complete.12" sweep	Each	4.00	1954.00	Rupees One Thousand Nine Hundred Fifty Four Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
184	Supplying capacitor type 48" sweep ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles, single phase AC supply confirminf to ISS-374-1979 and with double ball bearing system.Economy Model	Each	70.00	2184.00	Rupees Two Thousand One Hundred Eighty Four Only
185	Supplying wall mounting fan suitable to operate at single phase 230V AC Supply.400mm sweep	Each	2.00	2913.00	Rupees Two Thousand Nine Hundred Thirteen Only
186	Fixing all types and allcapacities fluorescent / false ceiling/spotlight/ CFLfittings indoor on the wall/ ceiling/rafters / girders using 23/0.0076" twin twisted RVC insulated wires, required nos of round blocks and clamps (if required) a)On wall/ceiling/Rafters/Girders	Each	141.00	113.00	Rupees One Hundred Thirteen Only
187	Fixing a ceiling/Wall mounting fan of all capacities and all types to the existing S hook together with supplying and fixing a 5 ampers ceiling rose, necessary length of 23 / 0.0076 inch PVC insulated twin twisted copper wire and wiring completely.	Each	76.00	160.00	Rupees One Hundred Sixty Only
188	Fixing charges of post top/Gate/Garden fitting/ LED on the existing CI/ GI or any other pipe using required size of reducer, wiring using suitable wires etc., complete.	Each	2.00	167.00	Rupees One Hundred Sixty Seven Only
189	Supplying and drawing PVC Flexible one pair telephone unarmoured tinned copper cable - 3 Pair	Rmtr	500.00	18.00	Rupees Eighteen Only
190	Supplying and drawing PVC Insulated Gas injected physical Foam jelly floaded co-Axial TV Cable RG-6	Rmtr	500.00	40.00	Rupees Forty Only
191	Supplying & Drawing UTP- CAT 6E-LAN Cable Group- A	Rmtr	500.00	26.00	Rupees Twenty Six Only
192	Supplying & fixing of network switches. 24 Port Gigabyte (Manageable)	Each	1.00	36382.00	Rupees Thirty Six Thousand Three Hundred Eighty Two Only
193	Design Supplying , erecting testing and commissioning pf 13 passanger / hospital lift with speed of 1.0Mtr per second variable voltage, variable frequency drive, with or without machine room for the available well size, operating at 415V Three phase 50 cycles AC Supply powder coated or stainless steel car enterance door enclosures with flooring car illumination emergencey light intercom and fan as desired by the user, central opening / side opening door with or without attendant operantion, 7 segment display kids buttons call register indicator fireman ddrive, SS Handrails inside car full length infra-red curtain in car door automatic rescue device voice announciation in reginal languages braile buttons with one year warranty and maintenance. the work includes providing shaft scafolding, attending minor builder work such as making nitches of fixing of brackets guide rails, counter weights etc., including obtaining lift running liecence from the compentent authority.	Each	1.00	2568558.00	Rupees Twenty Five Lakh Sixty Eight Thousand Five Hundred Fifty Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
194	Supplying erection, testing and commissioning of 3Way 11KV Load Break switch with connected accessories, hardwares etc., suitable for outdoor type complete as per IS standard technical specification. LBS should be approved by BESCOM.	Each	1.00	306693.00	Rupees Three Lakh Six Thousand Six Hundred Ninety Three Only
195	Supplying erection, testing and commissioning of Load Break switch with 4 wire -(with neutral) metering cubicle and connected accessories, hardwares etc., suitable for outdoor type complete as per IS standard technical specification. LBS should be approved by BESCOM.	Each	1.00	367825.00	Rupees Three Lakh Sixty Seven Thousand Eight Hundred Twenty Five Only
196	Supplying, erection, testing and commissioning100KVA Capacity Copper wound distribution transformer 11KV/433V with Off Load Tap Switch, Buchholtz relay winding temperature indicator, oil temperature indicator, marshalling box with wiring, magnetic oil level indicator with +5% to -10% steps of 2.5% with HT and LT cable end boxes including all standard accessories as per latest IS standard technical specification. HT Cables	Each	1.00	377841.00	Rupees Three Lakh Seventy Seven Thousand Eight Hundred Forty One Only
197	Supplying and laying of high tension 11KV cable dry curing & dry cooling with true triple extrusion, simultaniously through a single common head, 3core under ground XLPE cable having stranded compact circular aluminium conductor, screened insulated, insulation screened with extruded semiconducting compound in combination with copper tape, core laid up inner sheathe of PVC tape GI flat strip armoured and overall PVC sheathed with specified IS 7098/11/85 with latest amendments & confirming to the GTP of Group-A	Rmtr	50.00	1195.00	Rupees One Thousand One Hundred Ninety Five Only
198	Supplying and making 11KV(E) Extruded "X" linked for tubing & moulded & cross linked components using heat shrink stress control tube having high permitivity XLPE terminations- INDOOR & OUTDOOR JOINTING KIT & confirming to the GTP OUT DOOR 3Cx/95/120Sqmm	Kit	2.00	11619.00	Rupees Eleven Thousand Six Hundred Nineteen Only
199	IN DOOR 3Cx95/120Sqmm	Kit	6.00	9625.00	Rupees Nine Thousand Six Hundred Twenty Five Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
200	TT Kiosk Panel Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. Protection of overload and short circuit with the thermal magnetic/micro processor release and earth fault as per IS -13947 (leu=les) 320 -400Amps 4Pole 50kA	Each	1.00	28175.00	Rupees Twenty Eight Thousand One Hundred Seventy Five Only
201	Supplying, fixing of LED type panel board indicating lamp with required colour suitable for 220VA.C 50HZ 12/24V DC.	Each	3.00	508.00	Rupees Five Hundred Eight Only
202	Supplying 100 amps rated 3phase with neutral bus bar using requiemedcapacity electrolyticaluminium strips covered with heat shrinkable couloured PVC sleeve, mounted on phenolic/FRP/DMC insulator wheih are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete 100Amps 4x50x10mm Alluminium Strips	Rmtr	3.00	2454.00	Rupees Two Thousand Four Hundred Fifty Four Only
203	Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint	Rmtr	26.00	546.00	Rupees Five Hundred Forty Six Only
204	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover,equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 14SWG	Sq Cm	56000.00	0.54	Fifty Four Paise Only
205	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc.and fixing on existing wood or metal box using N.F. screws.	Sq Cm	6000.00	0.36	Thirty Six Paise Only
206	Main Panel -Annexure-B ,Incoming Supplying of On load change over switches 4poles, AC- 23A duty, 415V, 50Hz, AC supply, 400Amps	Each	1.00	33500.00	Rupees Thirty Three Thousand Five Hundred Only
207	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete, 320 -400Amps 4Pole 50kA	Each	1.00	28175.00	Rupees Twenty Eight Thousand One Hundred Seventy Five Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
208	Supplying, fixing and wiring earth leakage relay with core balanced current transformer suitable for single phase 50 Hz AC with latest microcontroller based, digital readout of pecentage leakage current, programable delay/auto/manual reset facility suitable to mount on DIN rail/ flush mounting on panel board.	Each	1.00	9194.00	Rupees Nine Thousand One Hundred Ninety Four Only
209	Supplying of multi function digital Meter with three line back light LCD type display of voltage, Current, frequency,Power, power factor,KVA, KWH,KVAR suitable for 3 phase, 4 wire LT network with IP 54 degree of protection and completely wired as required with communication port and class 0.5s accuracy.	Each	1.00	9199.00	Rupees Nine Thousand One Hundred Ninety Nine Only
210	Supplying, fixing and wiring 50/5 to 400/5 Amps 5VA burden Current Transformer. Class 0.5 accurecy with tape wound	Each	3.00	555.00	Rupees Five Hundred Fifty Five Only
211	Supplying, fixing of LED type panel board indicating lamp with required colour suitable for 220VA.C 50HZ 12/24V DC.	Each	3.00	508.00	Rupees Five Hundred Eight Only
212	Supplying 400 amps rated 3phase with neutral bus bar using requiemedcapacity electrolyticaluminium strips covered with heat shrinkable couloured PVC sleeve, mounted on phenolic/FRP/DMC insulator whcih are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete. 400Amps 4x50x10mm Alluminium Strips	Rmtr	6.00	4395.00	Rupees Four Thousand Three Hundred Ninety Five Only
213	Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete.125Amps 4Pole 25kA	Each	1.00	8474.00	Rupees Eight Thousand Four Hundred Seventy Four Only
214	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, e nergy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 63A TPN MCB	Each	12.00	2225.00	Rupees Two Thousand Two Hundred Twenty Five Only
215	Supplying ,fixing and wiring heavy duty low voltage capacitors conforming to IS 2834. 3 phase, 400/440 volts grade, for power factor improvement of rotating machinery. Cost per KVAR.	KVAR	1.00	476.00	Rupees Four Hundred Seventy Six Only
216	Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.	Rmtr	30.00	546.00	Rupees Five Hundred Forty Six Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
217	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover,equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 14SWG	Sq Cm	400000.00	0.54	Fifty Four Paise Only
218	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc.and fixing on existing wood or metal box using N.F. screws.	Sq Cm	40000.00	0.36	Thirty Six Paise Only
219	Lift Panel, Annexure-E, Incoming,Supplying and fixing Moulded Case Circuit Breaker (MCCB) over the existing wood/panel board using necessary screws, bolts, nuts and wiring complete. 63Amps 4Pole 25kA	Each	1.00	6677.00	Rupees Six Thousand Six Hundred Seventy Seven Only
220	Supplying, fixing and wiring 3 Phase Digital Ammeter/Voltmeter	Each	2.00	1407.00	Rupees One Thousand Four Hundred Seven Only
221	Supplying, fixing and wiring rotary selector switch suitable for ammeter	Each	1.00	198.00	Rupees One Hundred Ninety Eight Only
222	Supplying, fixing and wiring rotary selector switch suitable for voltmeter	Each	1.00	161.00	Rupees One Hundred Sixty One Only
223	Supplying, fixing and wiring 50/5 to 400/5 Amps 5VA burden Current Transformer. Class 0.5 accurecy with tape wound	Each	3.00	555.00	Rupees Five Hundred Fifty Five Only
224	Supplying, fixing of LED type panel board indicating lamp with required colour suitable for 220VA.C 50HZ 12/24V DC.	Each	3.00	508.00	Rupees Five Hundred Eight Only
225	Supplying 100 amps rated 3phase with neutral bus bar using requiemedcapacity electrolyticaluminium strips covered with heat shrinkable couloured PVC sleeve, mounted on phenolic/FRP/DMC insulator whcih are mounted on powder coated 40x6mm M.S.flat frame work in existing panel board. The bus bar shall have suitable holes for termination of incoming and outgoing cables as per IS specification with necessary bolts, nuts and washers etc., complete.100Amps 4x30x6mm Alluminium Strips	Rmtr	0.50	2454.00	Rupees Two Thousand Four Hundred Fifty Four Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
226	OutGoings:-Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 5-32A SP MCB	Each	3.00	480.00	Rupees Four Hundred Eighty Only
227	OutGoings:-Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 5-32A DP MCB	Each	3.00	976.00	Rupees Nine Hundred Seventy Six Only
228	OutGoings:-Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' type curve, indicator ON/OFF, energy cross-3 with short circuit breaking capacity of 10K and complete wiring as required. 40-63A TPN MCB	Each	1.00	2225.00	Rupees Two Thousand Two Hundred Twenty Five Only
229	Supplying and fixing angle iron frame work fabricated out of M.S.angle iron.. and M.S. flat ... with bolts, washers etc., and painted with 2 coats of red oxide and then two coats of approved paint.40x40x6mm	Rmtr	14.00	546.00	Rupees Five Hundred Forty Six Only
230	Fabricating supplying and mounting MS box made out... SWG suitable for floor/wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover,equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete 14SWG	Sq Cm	32000.00	0.54	Fifty Four Paise Only
231	Supplying and fixing hylum brand hand plastic sheet 3mm thick with necessary nitches for fixing switches, regulators etc.and fixing on existing wood or metal box using N.F. screws.	Sq Cm	6000.00	0.36	Thirty Six Paise Only
232	Chemical earthing for grounding, conduits, IC cutouts & other equipments on the meter board by using copper bonded / SS rod with earth enhancing beakfill compound which is noncorrosive thermally conductive, potential to permissibel limits, superior fault conduction capacity, non toxic, weather resistance & capable of achieving Ohmic value less than one Ohm. Using 10ft copper bonded rod with backfill compound	Each	16.00	8621.00	Rupees Eight Thousand Six Hundred Twenty One Only
233	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required.GI Strip 25x3mm	Rmtr	30.00	89.00	Rupees Eighty Nine Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
234	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required.GI Strip 25x6mm	Rmtr	20.00	136.00	Rupees One Hundred Thirty S Only
235	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required.Copper Strip 25x3mm	Rmtr	10.00	601.00	Rupees Six Hundr One Only
236	Supplying and running of GI/copper strips for grounding connections, using necessary fixing materials as required.Copper Strip 25x6mm	Rmtr	10.00	1170.00	Rupees One Thousand One Hundred Seventy Only
237	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class Class 'A' PVC cable 4Core 10Sqmm	Rmtr	50.00	137.00	Rupees One Hundred Thirty Seven Only
238	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tap armoured cable with PVC outer sheathing 1.1 KV class Class 'A' PVC cable 3.5Core 150Sqmm	Rmtr	50.00	756.00	Rupees Seven Hundred Fifty Six Only
239	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required. In existing trench/duct 6sqmm to 16sqmm	Rmtr	85.00	12.00	Rupees Twelve Only
240	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required.In existing trench/duct 25sqmm to 75sqmm	Rmtr	50.00	31.00	Rupees Thirty One Only
241	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required.On wall/structure 6sqmm to 16sqmm	Rmtr	15.00	36.00	Rupees Thirty Six Only
242	Labour charges for layingof 1.1 KVclass UG cable when supplied agency in existing trench GI pipe / stoneware pipe / on wall/ on pole as required.On wall/structure 185sqmm to 240sqmm	Rmtr	10.00	51.00	Rupees Fifty One Only
243	Digging of trench of 0.6m deep x 0.50 mtr wide refiling the trench to the required ground level and consolidating etc., complete.(As . per Civil SA KSAB 1 2, P-7) in soil (ordinary)	Rmtr	20.00	90.00	Rupees Ninety Only
244	Providing and filling sand in excavated trench to cover already laid UGcable to a depth of 150mm alround the cable.	Rmtr	20.00	118.00	Rupees One Hundred Eighteen Only
245	Providing and laying in position 100mm dia stone ware pipe in exisitng trench.	Rmtr	20.00	256.00	Rupees Two Hundred Fifty Six Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
246	Supplying and fixing of class A (mediumduty) GI pipe of wall thick ness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UGcable of 1.1 KVclass.	Rmtr	9.00	816.00	Rupees Eight Hundred Sixteen Only
247	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KVclass (metal only) 75 mm dia	Each	2.00	590.00	Rupees Five Hundred Ninety Only
248	Supplying and fiixing of heavy duty cable glands suitable for UG cable of 1.1 KVclass (metal only) 100mm dia	Each	5.00	1147.00	Rupees One Thousand One Hundred Forty Seven Only
249	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes 16Sqmm Long Barrel	Each	20.00	13.00	Rupees Thirteen Only
250	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes25Sqmm Long Barrel	Each	5.00	24.00	Rupees Twenty Four Only
251	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes150Sqmm Long Barrel	Each	5.00	278.00	Rupees Two Hundred Seventy Eight Only
252	Supplying tinned copper lugs and crimping and wiring to terminal point for wire of the following sizes185Sqmm Long Barrel	Each	4.00	389.00	Rupees Three Hundred Eighty Nine Only
253	Supplying and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6mm welded together and fixed in CC (1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25cms. Including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete)	Rmtr	36.00	1066.00	Rupees One Thousand Sixty Six Only
254	Providing chain link fencing 50mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint	Sqm	40.00	888.00	Rupees Eight Hundred Eighty Eight Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
255	Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Nos	8.00	6369.00	Rupees Six Thousand Three Hundred Sixty Nine Only
256	Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Unit	8.00	5383.00	Rupees Five Thousand Three Hundred Eighty Three Only
257	Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Nos	16.00	4824.00	Rupees Four Thousand Eight Hundred Twenty Four Only
258	Providing and fixing white vitreous china clay, flat back or half stall urinal basin of size 580x380x350mm in the range of two with 7.5 litres P.V.C automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps, C.I. trap with outlet grating and other couplings in C.P brass painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Each	12.00	10323.00	Rupees Ten Thousand Three Hundred Twenty Three Only
259	Providing fixing C.P brass towel rail 600mm length, 20mm dia with C.P brackets,fixed to wooden cleats with C.P brass screws including cost of materials,labour complete as per specifications. Make: Jaquar, Range-continental , Model No-1121	Unit	12.00	881.00	Rupees Eight Hundred Eighty One Only
260	KSRB 11-15.1 : Providing and fixing 600x450mm bevellead edge mirror of superior glass with 6mm hard board backing and fixed to wooden cleats with C.P screws, washers, including cost of materials, labour complete as per specifications.	Unit	16.00	1553.00	Rupees One Thousand Five Hundred Fifty Three Only

Signature of the contractor

Executive Engineer
(Project) RRNagara Zone
BBMP

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
261	Supply, fixing, testing and commissioning of 20 mm CP brass bib cock with wall flange and suitable length extension pipe etc,. complete as per specification.	Nos	16.00	302.00	Rupees Three Hundred Two Only
262	Providing and fixing in position brass stop cock of approved quality 20 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. etc,. complete as per specification.	Nos	16.00	199.00	Rupees One Hundred Ninety Nine Only
263	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot). - 10cms x 7.5cms	Nos	32.00	310.00	Rupees Three Hundred Ten Only
264	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m.after breaking of clods complete as per specification.	Cum	36.00	235.00	Rupees Two Hundred Thirty Five Only
265	Providing & fixing Chorinated Poly Venyl Chloride (CPVC) 20 mm dia pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00m spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and cost of cutting chases and making good the same including testing of joints complete. (concealed work including cutting chases and good the walls etc.)	Rmtr	160.00	261.00	Rupees Two Hundred Sixty One Only
266	Providing and fixing chorinated poly venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (External work) 20mm dia	Rmtr	100.00	155.00	Rupees One Hundred Fifty Five Only

Executive Engineer
(Project) RRNagara Zone
BBMP

Signature of the contractor

Scanned by CamScanner

Sl.No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
267	Providing and fixing chorinated poly venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (External work25mm dia	Rmtr	150.00	205.00	Rupees Two Hundred Five Only
268	Providing and fixing chorinated poly venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (External work32mm dia	Rmtr	180.00	267.00	Rupees Two Hundred Sixty Seven Only
269	KSRB13-6.3-7: Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) 32mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. - do'- with 32 mm dia (Screwed ends)	Nos	2.00	1208.00	Rupees One Thousand Two Hundred Eight Only
270	KSRB13-6.4-2 : Providing and fixing in position brass ball valve high or low pressure with plastic float of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 25mm dia nominal	Nos	2.00	752.00	Rupees Seven Hundred Fifty Two Only
271	Supply, installation, testing and commissioning electrically driven SUBMERSIIBLE pump of capacity 2HP / 1.5 KW with 12 stages Single phase, 50Hz, 400/440V AC supply with necessary non-return valves, butterfly valves,,Pressure gauge & Pressure switch with inter-connecting wiring etc., complete as per standard design. (For pumping the domestic water from the underground sump to the overhead water tank). Make/Brand :ATALANTA,SUGUNA, C.R.I.,KIRLOSKAR AND OTHER EQUIVALENT PUMPS	Nos	1.00	19243.00	Rupees Nineteen Thousand Two Hundred Forty Three Only
272	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer Black or Blue and inner White layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications.	Each	2.00	10549.00	Rupees Ten Thousand Five Hundred Forty Nine Only

Executive Engineer
(Project) RRNagara Zone

Scanned by CamScanner

No	Description of work	Unit	Qty	In Figures (Rs.)	In Words (Rs.)
	2	3	4	5	6
1	kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications 110 mm dia and 110 mm dia Rain water pipes	Rmtr	180.00	511.00	Rupees Five Hundred Eleven Only
273	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 110mm outer dia 110 mm dia for sewer line	Rmtr	98.00	854.00	Rupees Eight Hundred Fifty Four Only
274	Providing and fixing to wall, ceiling and floor unplasticised PVC pipes 10.00 kgf/sq.cm working pressure chemp plast / Wavin or equivalent make with pipe fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials,with 110mm outer dia 160 mm Dia	Rmtr	50.00	1800.00	Rupees One Thousand Eight Hundred Only
275	Constructing brick masonry inspection chamber 600 x 600mm, and 450mm depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I cover with frame (light duty) 600 x 600mm IC for Sewage	Each	16.00	11116.00	Rupees Eleven Thousand One Hundred Sixteen Only
276					

Signature of the Contractor

Executive Engineer (Project)
Rajarajeshwarinagara Zone
B.B.M.P

Executive Engineer

Scanned by CamScanner